

Hydrotest

- Procedures should include provisions for cold weather testing (if not see next slide)
- Pressures should be maintained at least 8 hours for buried piping. Any pressure decline should be investigated. A second pressure test may be warranted. (See chart of failed test)